

Vipac Engineers and Scientists Limited

279 Normanby Rd, Port Melbourne, VIC 3207, Australia Private Bag 16, Port Melbourne, VIC 3207, Australia t. +61 3 9647 9700 | f. +61 3 9646 4370 | e. melbourne@vipac.com.au w. www.vipac.com.au | A.B.N. 33 005 453 627 | A.C.N. 005 453 627

# Vipac Engineers & Scientists

## Pace Development Group Pty Ltd

## 160 Whitehorse Road Stage 2 - Acoustics Town Planning

## **Acoustic Town Planning Report**

PLANNING AND ENVIRONMENT ACT 1987 WHITEHORSE PLANNING SCHEME

31/07/2019

#### ADVERTISED MATERIAL

CITY OF WHITEHORSE 'This copied document is made available for the sole purpose of enabling its consideration and review as part of a planning permit under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach copyright.'

30U-18-0958-TRP-6757059-2

5 March 2019



DOCUMENT NO: 30U-18-0958-TRP-6757059-2 PREPARED FOR: PrepARED FOR: PrepARED FOR: PrepARED FOR: PREPARED BY: PrepareD BY: Australia CONTACT: Michael Holah Tel: 1300722334 Tel: +61 3 9647 9700 Fax: Fax: Fax: +61 3 9647 9700 Fax: +61 3 9646 4370 PREPARED BY: Author: Date: 5 Mar 2019 Matthew Nolan Project Engineer REVIEWED BY: Reviewer: Date: 5 Mar 2019 Davyn Mather Project Engineer AUTHORISED BY: Revision No. Date Issued Conrad Williams Team Leader REVISION HISTORY Revision No. Date Issued Conrad Williams Team Leader REVISION HISTORY Revision No. Date Issued Conrad Williams Team Leader REVISION HISTORY Revision No. Date Issued Conrad Williams Team Leader Conrad Williams Team Leader DISTRIBUTION Copy No. Location 1 Project Conrat Uncontrolled Copy Control Uncontrolled Copy Control (PDF Format) Uncontrolled Copy Control (PDF Format) Controlled Cont Contro	Report Title: Acoustic Town Planning Report Job Title: 160 Whitehorse Road Stage 2 - Acoustics Town Planning				
Pace Development Group Pty Ltd       Vipac Engineers and Scientists Limited 279 Normanby Rd, Port Melbourne, VIC 3207, Australia         CONTACT: Michael Holah       Australia         Tel: 1300722334       Tel: +61 3 9647 9700         Fax:       Fax: +61 3 9646 4370         PREPARED BY:       Matthew Nolan Project Engineer         Author:       Date: 5 Mar 2019         Matthew Nolan Project Engineer       Date: 5 Mar 2019         Reviewer:       Date: 5 Mar 2019         Datyn Mather Project Engineer       Date: 5 Mar 2019         AUTHORISED BY:       Date: 5 Mar 2019         Reviewer:       Date: 5 Mar 2019         Conrad Williams Team Leader       Date: 5 Mar 2019         Revision No.       Date Issued       Reason/Comments         0       5/03/2019       Initial Issue         1       2       Distribution         2       Distribution       Corpy No	DOCUMENT NO: 30U-18-095	8-TRP-6757059-2	REPORT CODE: TRP		
Australia     279 Normanby Rd, Port Melbourne, VIC 3207, Australia       CONTACT: Michael Holah     Tel: +61 3 9647 9700       Fax:     Tel: +61 3 9646 4370       PREPARED BY:     Tel: +61 3 9646 4370       Author:     Date: 5 Mar 2019       Matthew Nolan Project Engineer     Date: 5 Mar 2019       Reviewer:     Date: 5 Mar 2019       Datyn Mather Project Engineer     Date: 5 Mar 2019       AUTHORISED BY:     Date: 5 Mar 2019       Reviewer:     Date: 5 Mar 2019       Datyn Mather Project Engineer     Date: 5 Mar 2019       Reviewer:     Date: 5 Mar 2019       Matthew Nolan Project Engineer     Date: 5 Mar 2019       Matther Project     Date: 5 Mar	PREPARED FOR:		PREPARED BY:		
Australia       Port Melbourne, VIC 3207,         Australia       Australia         CONTACT: Michael Holah       Tel: +61 3 9647 9700         Fax:       Tel: +61 3 9646 4370         PREPARED BY:       Date: 5 Mar 2019         Author:       Date: 5 Mar 2019         Matthew Nolan Project Engineer       Date: 5 Mar 2019         Reviewer:       Date: 5 Mar 2019         Date: 5 Mar 2019       Date: 5 Mar 2019         Authorikee BY: Project Engineer       Date: 5 Mar 2019         Authorikee BY: Project Engineer       Date: 5 Mar 2019         Reviewer:       Date: 5 Mar 2019         Date: 5 Mar 2019       Date: 5 Mar 2019         Revision No.       Conrad Williams Team Leader         Revision No.       Date Issued       Reason/Comments         0       5/03/2019       Initial Issue         1       Project       Juncontrolled Copy         2       Distribution       Colation         1       Project       Juncontrolled Copy         3       Client (PDF Format)       Uncontrolled Copy	Pace Development Group Pty	Ltd	Vipac Engineers and Scientists Limited		
Australia       Australia         CONTACT: Michael Holah       Tel: +61 3 9647 9700         Fax:       Tel: +61 3 9646 4370         Fax:       Date: 5 Mar 2019         Fax:       Date: 5 Mar 2019         Matthew Nolan       Project Engineer         Project Engineer       Date: 5 Mar 2019         Beviewer:       Date: 5 Mar 2019         Davyn Mather       Project Engineer         Project Engineer       Date: 5 Mar 2019         AutHORISED BY:       Date: 5 Mar 2019         Reviewer:       Date: 5 Mar 2019         Corrad Williams       Date: 5 Mar 2019         Revision No.       Date Issued       Reason/Comments         0       5/03/2019       Initial Issue         1       Distribution       Copy No			279 Normanby Rd,		
CONTACT: Michael Holah       Tel: +61 3 9647 9700         Fax:       Tel: +61 3 9646 4370         PREPARED BY:       Date: 5 Mar 2019         Author:       Date: 5 Mar 2019         Project Engineer       Date: 5 Mar 2019         Reviewer:       Date: 5 Mar 2019         Davyn Mather       Project Engineer         AUTHORISED BY:       Date: 5 Mar 2019         Conrad Williams       Date: 5 Mar 2019         Conrad Williams       Date: 5 Mar 2019         Team Leader       Date: 5 Mar 2019         Revision No.       Date Issued       Reason/Comments         0       5/03/2019       Initial Issue         1       Copy No       Location         1       Project       Juncontrolled Copy         3       Client (PDF Format)       Uncontrolled Copy			Port Melbourne, VIC 3207,		
Tel: 1300722334       Tel: +61 3 9647 9700         Fax:       Date: 5 Mar 2019         Author:       Date: 5 Mar 2019         Author:       Date: 5 Mar 2019         PREPARED BY:       Date: 5 Mar 2019         Reviewer:       Date: 5 Mar 2019         Davyn Mather       Project Engineer         Project Engineer       Date: 5 Mar 2019         AUTHORISED BY:       Date: 5 Mar 2019         Conrad Williams       Date: 5 Mar 2019         Team Leader       Date: 5 Mar 2019         Revision No.       Date Issued         0       5/03/2019         1       Sologian Comments         1       Date         1       Project         2       Distribution         Copy No       Location         1       Project         2       Client (PDF Format)       Uncontrolled Copy         3       Uncontrolled Copy	Australia		Australia		
Fax:       Fax: +61 3 9646 4370         PREPARED BY:       Date: 5 Mar 2019         Author:       Date: 5 Mar 2019         Matthew Nolan       Project Engineer         REVIEWED BY:       Date: 5 Mar 2019         Reviewer:       Date: 5 Mar 2019         Davyn Mather       Project Engineer         AUTHORISED BY:       Date: 5 Mar 2019         Conrad Williams       Date: 5 Mar 2019         Conrad Williams       Date: 5 Mar 2019         Revision No.       Date Issued       Reason/Comments         0       5/03/2019       Initial Issue         1       Coation       Copy No.       Location         1       Project       Uncontrolled Copy         3       Client (PDF Format)       Uncontrolled Copy	<b>CONTACT:</b> Michael Holah				
PREPARED BY:       Date: 5 Mar 2019         Author:       Date: 5 Mar 2019         Matthew Nolan       Project Engineer         REVIEWED BY:       Date: 5 Mar 2019         Reviewer:       Date: 5 Mar 2019         Dayyn Mather       Project Engineer         AUTHORISED BY:       Date: 5 Mar 2019         AUTHORISED BY:       Date: 5 Mar 2019         Conrad Williams       Team Leader         REVISION HISTORY       Reason/Comments         0       5/03/2019       Initial Issue         1       2       Uncontrolled Copy         DISTRIBUTION       Location       Initial Issue         1       Project       Jate: 1         2       Colient (PDF Format)       Uncontrolled Copy         3       Substantial Sub	Tel: 1300722334		Tel: +61 3 9647 9700		
Author:       Date: 5 Mar 2019         Matthew Nolan Project Engineer       Date: 5 Mar 2019         REVIEWED BY: Reviewer:       Datyn Mather Project Engineer         AUTHORISED BY:       Datyn Mather Project Engineer         AUTHORISED BY:       Date: 5 Mar 2019         REVISION HISTORY       Date Issued Stoar 2019         Revision No.       Date Issued 5/03/2019         Revision No.       Date Issued Stoar 2019         1       External of the stoar 2019         1       External cader         DISTRIBUTION       Location         1       Project         2       External cader         DISTRIBUTION       Location         1       Project         2       Uncontrolled Copy         3       Client (PDF Format)	Fax:		<b>Fax</b> : +61 3 9646 4370		
Matthew Nolan Project Engineer       Date 3 Mat Notan Project Engineer         Reviewer:       Date: 5 Mar 2019         Davyn Mather Project Engineer       Date: 5 Mar 2019         AUTHORISED BY:       Date: 5 Mar 2019         AUTHORISED BY:       Date: 5 Mar 2019         Revision No.       Conrad Williams Team Leader         Revision No.       Date Issued         0       5/03/2019         1       Initial Issue         1       Cocation         1       Project         1       Project         2       Uncontrolled Copy         3       Gient (PDF Format)	PREPARED BY:				
Project Engineer         REVIEWED BY:       Date: 5 Mar 2019         Reviewer:       Davyn Mather Project Engineer         AUTHORISED BY:       Date: 5 Mar 2019         Revision BY:       Date: 5 Mar 2019         Revision NO:       Conrad Williams Team Leader         Revision No.       Date Issued       Reason/Comments         0       Date Issued       Reason/Comments         1       Corrad Williams       Corrad Williams         2       Conrad Williams       Comments         0       Date Issued       Reason/Comments         0       Distribution       Corrad Williams         2       Comment       Comment         1       Coetion       Coetion         1       Project       Comment         2       Client (PDF Format)       Uncontrolled Copy         3       Comment       Comment	Author:		Date: 5 Mar 2019		
Project Engineer         REVIEWED BY:       Date: 5 Mar 2019         Reviewer:       Davyn Mather Project Engineer         AUTHORISED BY:       Date: 5 Mar 2019         Revision BY:       Date: 5 Mar 2019         Revision NO:       Conrad Williams Team Leader         Revision No.       Date Issued       Reason/Comments         0       Date Issued       Reason/Comments         1       Corrad Williams       Corrad Williams         2       Conrad Williams       Comments         0       Date Issued       Reason/Comments         0       Distribution       Corrad Williams         2       Comment       Comment         1       Coetion       Coetion         1       Project       Comment         2       Client (PDF Format)       Uncontrolled Copy         3       Comment       Comment		Matthew Nolan			
REVIEWED BY:       Date: 5 Mar 2019         Project Engineer       Date: 5 Mar 2019         AUTHORISED BY:       Date: 5 Mar 2019         Conrad Williams Team Leader       Date: 5 Mar 2019         REVISION HISTORY       Reason/Comments         Revision No.       Date Issued       Reason/Comments         0       5/03/2019       Initial Issue         1       Coation       Initial Issue         1       Project         2       Uncontrolled Copy         3       Uncontrolled Copy					
Reviewer: Date: 5 Mar 2019 Davyn Mather Project Engineer  AUTHORISED BY: Corrad Williams Team Leader  REVISION HISTORY Revision No. Date Issued Date I	REVIEWED BY:	r rojoot Engineer			
Davyn Mather Project Engineer         AUTHORISED BY:         Conrad Williams Team Leader         REVISION HISTORY         Revision No.         Date Issued         703/2019         Initial Issue         1         2         DISTRIBUTION         Copy No         1         Project         2         DISTRIBUTION         Copy No         1         Project         2         1         2         DISTRIBUTION         Copy No         1       Project         2       Client (PDF Format)       Uncontrolled Copy         3			Date: 5 Mar 2019		
Project Engineer         AUTHORISED BY:       Date:5 Mar 2019         Conrad Williams Team Leader       Date:5 Mar 2019         REVISION HISTORY       Feason/Comments         Revision No.       Date Issued       Reason/Comments         0       Date Issued       Initial Issue         1       Example       Example         1       Project       Example         2       Example       Example         DISTRIBUTION       Example       Example         1       Project       Example         2       Example       Example         DISTRIBUTION       Example       Example         1       Project       Example         2       Example       Example         3       Example       Example					
AUTHORISED BY:       Date:5 Mar 2019         Conrad Williams Team Leader       Team Leader         REVISION HISTORY       Reason/Comments         0       5/03/2019       Initial Issue         1       2         DISTRIBUTION Copy No       Location         1       Project         2       Client (PDF Format)       Uncontrolled Copy		Davyn Mather			
Date:5 Mar 2019         Conrad Williams Team Leader         REVISION HISTORY         Revision No.       Date Issued       Reason/Comments         0       5/03/2019       Initial Issue         1       Copy No.       Location         1       Project       Uncontrolled Copy         3       Client (PDF Format)       Uncontrolled Copy		Project Engineer			
Conrad Williams Team Leader         REVISION HISTORY         Revision No.       Date Issued         0       Date Issued         5/03/2019       Initial Issue         1       Initial Issue         2       Initial Issue         DISTRIBUTION       Location         1       Project         2       Client (PDF Format)         Uncontrolled Copy       Given to the topology	AUTHORISED BY:				
Team LeaderREVISION HISTORYRevision No.Date IssuedReason/Comments05/03/2019Initial Issue15/03/2019Initial Issue2			Date:5 Mar 2019		
Team LeaderREVISION HISTORYRevision No.Date IssuedReason/Comments05/03/2019Initial Issue15/03/2019Initial Issue2					
REVISION HISTORYRevision No.Date IssuedReason/Comments05/03/2019Initial Issue12DISTRIBUTIONCopy NoLocation1Project2Client (PDF Format)Uncontrolled Copy3-					
Revision No.Date IssuedReason/Comments05/03/2019Initial Issue12DISTRIBUTIONCopy No1Project2Client (PDF Format)Uncontrolled Copy3		Team Leader			
05/03/2019Initial Issue12DISTRIBUTIONCopy NoLocation1Project2Client (PDF Format)Uncontrolled Copy3					
1       2         DISTRIBUTION       Location         1       Project         2       Client (PDF Format)       Uncontrolled Copy         3       Uncontrolled Copy	Revision No.				
2 DISTRIBUTION Copy No Location 1 Project 2 Client (PDF Format) Uncontrolled Copy 3	0	5/03/2019	Initial Issue		
DISTRIBUTION       Location         1       Project         2       Client (PDF Format)       Uncontrolled Copy         3       Uncontrolled Copy	1				
Copy NoLocation1Project2Client (PDF Format)Uncontrolled Copy3	2				
1     Project       2     Client (PDF Format)     Uncontrolled Copy       3	DISTRIBUTION				
2 Client (PDF Format) Uncontrolled Copy 3	Сору No	Location			
3	1	Project			
	2	Client (PDF Format)	Uncontrolled Copy		
KEYWORDS:	3				
	KEYWORDS:				

NOTE: This is a controlled document within the document control system. If revised, it must be marked SUPERSEDED and returned to the Vipac QA Representative. This document contains commercial, conceptual and engineering information that is proprietary to Vipac Engineers & Scientists Ltd. We specifically state that inclusion of this information does not grant the Client any license to use the information without Vipac's written permission. We further require that the information not be divulged to a third party without our written conse



TAE	BLE O	FCONTENTS
1	IN	TRODUCTION4
2	RE	EFERENCES4
3	DF	RAWINGS4
4	DE	EVELOPMENT DESCRIPTION
5	NC	DISE MEASUREMENTS6
6	AC	COUSTIC DESIGN CRITERIA8
6.1	Re	ecommended Interior Noise Levels
6.1	No	bise Emission from the Development9
	6.1.1	Plant Noise at Residential Properties9
	6.1.2	Plant Servicing Individual Dwellings9
	6.1.3	Plant noise impact on communal areas9
	6.1.4	Plant noise within any affected commercial properties10
	6.1.5	Carpark Access Gates
	6.1.6	ALDI Supermarket and retail store
6.2	De	elivery trucks/loading bays
6.3	Ga	arbage trucks
6.4	NC	CC Requirements for Internal Partitions 12
	6.4.1	NCC requirements for inter-tenancy walls
	6.4.2	NCC requirements for floors
	6.4.3	NCC Requirements for Services Ducts and Pipes 13
7		JILDING FAÇADE GLAZING RECOMMENDATIONS 14
8	CC	DNCLUSION
		Appendix A Glossary
		Appendix B Instrumentation



## **1 INTRODUCTION**

Vipac Engineers & Scientists Ltd (ViPAC) has been engaged by *Pace Development Group Pty Ltd* to provide an Acoustic Report for Stage 2 of Town Planning for the proposed development at **160 Whitehorse Road**, **Blackburn**, **Victoria**.

### 2 REFERENCES

- State Environment Protection Policy (Control of Noise from Industry, Commerce and Trade) No. N-1 (SEPP N-1), Environment Protection Authority, Victoria, No. S31, 16/5/1989 Gazette 15/6/1989; as varied 15/9/1992, No. G37, gazette 23/9/1992; as varied 31/10/2001, No. S183, Gazette 31/10/2001
- AS/NZS 2107:2016 Acoustics Recommended Design Sound Levels and Reverberation Times for Building Interiors
- Better Apartments Design Standards Victoria State Government
- Noise Control Guidelines Publication 1254, Environment Protection Authority, Victoria
- World Health Organisation Guidelines for Community Noise, MNB-1Q DOC2, April 1999
- 160 Whitehorse Rd, Blackburn, Town Planning Submission Stage 02, 08/02/2019

Acoustic terminology is given in Appendix A.

### **3 DRAWINGS**

Table 3-1: Development drawings

Drawing Title	Drawing Number	Revision	Date
Stage 02 Basement 5	TP-03	А	08/02/2019
Stage 02 Basement 4	TP-04	А	08/02/2019
Stage 02 Basement 3	TP-05	А	08/02/2019
Stage 02 Basement 2	TP-06	А	08/02/2019
Stage 02 Basement 1	TP-07	А	08/02/2019
Ground Floor	TP-08	А	08/02/2019
Stage 02 Level 1	TP-09	А	08/02/2019
Stage 02 Level 2	TP-10	А	08/02/2019
Stage 02 Level 3	TP-11	А	08/02/2019
Stage 02 Level 4	TP-12	А	08/02/2019
Stage 02 Level 5	TP-13	А	08/02/2019
Stage 02 Level 6	TP-14	А	08/02/2019
Stage 02 Level 7	TP-15	А	08/02/2019
Stage 02 Parapet	TP-16	А	08/02/2019



## 4 DEVELOPMENT DESCRIPTION

Stage 2 of the proposed development at 160 Whitehorse Road, Blackburn encompasses a building that contains office space, an ALDI Supermarket, retail stores and residential apartments. Floors contain the following:

- Basement 2,3,4 and 5 contain car parks •
- Basement 1 contains an ALDI Supermarket and car parks
- Ground floor consists of retail stores, office spaces (approximately 12,000m<sup>2</sup> in total) and a potential sub tenancy
- Level 1 to 5 consists of apartments and office space •
- Level 6 consists of apartments only .

Figure 4-1 shows the planned site layout and Figure 4-2 shows the current site location.



Figure 4-1: Site Plan





Figure 4-2: Site location

## 5 NOISE MEASUREMENTS

Noise measurements for background noise and road traffic noise were made on the 12<sup>th</sup> of November 2018 in accordance with *SEPP N-1* during the Day (0700 – 1800). To obtain the Evening (1800 – 2200) and Night (2200 – 0700) periods two loggers were installed from the 5<sup>th</sup> to the 7<sup>th</sup> of November 2018. Weather conditions at the site during measurements were dry with light winds. A calibration check of the sound level meter was performed before and after each measurement set, no significant drift was noted. Figure 5-1 shows the locations for noise measurements. All measurement locations were sufficiently distant from reflective surfaces such that nearfield level corrections were not required.

Instrumentation used for the noise measurements is presented in Appendix B.



Pace Development Group Pty Ltd 160 Whitehorse Road Stage 2 - Acoustics Town Planning Acoustic Town Planning Report




Figure 5-1: Measurement locations



## 6 ACOUSTIC DESIGN CRITERIA

#### 6.1 RECOMMENDED INTERIOR NOISE LEVELS

Australia and New Zealand standard *AS/NZS 2107* recommends design criteria for conditions affecting the acoustic environment within occupied spaces. The Victorian *Better Apartments Design Standards* also provide acoustic design criteria for apartments. Design sound pressure levels (SPL) for residential and commercial occupancies are given in Table 6-1. The selected design levels for this project are based on *Better Apartment Design Standards*. These values are applicable to steady state or quasi-steady state sounds and are the reference criteria for selection and assessment of building components that exclude noise both external to the building (e.g., traffic noise, industrial noise), and within the building (e.g., building services noise).

<b>T</b>	Design Sound Level Range, L <sub>Aeq</sub> [dBA]		
Type of Occupancy	AS/NZS 2107	Better Apartments	
	Public Buildings		
Supermarkets	< 55	-	
Small retail stores (general)	< 50	-	
General office areas	40 to 45	-	
Apartments (in inner city areas or entertainment districts or near major roads)			
Living areas	-	L <sub>Aeq,16h(0600-2200)</sub> 40	
Sleeping areas (night time)	-	L <sub>Aeq,8h(2200-0600)</sub> 35	
Apartment common areas (e.g. foyer, lift lobby)	45 to 50	-	

Table 6-1: Design sound levels for background noise, AS/NZS 2107 & Better Apartments Design Standards



#### 6.1 NOISE EMISSION FROM THE DEVELOPMENT

### 6.1.1 PLANT NOISE AT RESIDENTIAL PROPERTIES

Mechanical plant noise must be controlled at any affected residential properties in accordance with State Environmental Noise Policy *SEPP N-1*. Affected residential properties include apartments within the development, and residences in the vicinity of the development. According to the *SEPP N-1* policy environmental noise limits are determined based on a two part procedure – determination of the existing background noise levels (percentile sound pressure level L<sub>A90</sub>) and zoning levels (obtained from the town plan scheme map). Table 6-2 presents the SEPP N-1 limits calculated from the averaged background measurements taken during each period.

SEPP N-1 Period	Day of week/Time period		Zoning level	Background level, L <sub>90</sub>	Noise limit
Dav	Monday – Friday	0700hrs – 1800hrs	50	50 00	50
Day	59 Saturday 0700hrs – 1300hrs	62	59		
	Monday – Friday	1800hrs – 2200hrs		56	53
Evening	Saturday	1300hrs – 2200hrs	53		
Evening	Sunday & public holidays	0700hrs – 2200hrs	55	50	
Night	Monday – Sunday	2200hrs – 0700hrs	48	46	48

Table 6-2: SEPP N-1 limits for the development and surrounding residences [dBA]

Note: the developer will need to undertake a formal acoustic review by a suitably qualified engineer for all mechanical plant and equipment used in the development to ensure it complies with EPA guidelines.

#### 6.1.2 PLANT SERVICING INDIVIDUAL DWELLINGS

Noise emissions from any fixed domestic plant such as air conditioners shall be controlled to comply with EPA Noise Control Guidelines 1254. Noise from any fixed domestic plant must not be audible within a habitable room of any other residence (regardless of whether any door or window giving access to the room is open) during prohibited hours prescribed by the Environment Protection (Residential Noise) Regulations 2008.

Period	Hours	Criteria
Day/ Evening	7am - 10pm Monday – Friday 9am - 10pm Weekends & public holidays	Background L <sub>90</sub> + 5 dB(A)
Night	10pm - 7am Monday – Friday 10pm - 9am Weekends & public holidays	Inaudible within a habitable room of any other residence

Table 6-3: EPA 1254 conditions for domestic plant

The roof of the substation located on the ground floor should be constructed to achieve  $R_w + C_{tr} \ge 60$  dB. Once relevant data is available a SEPP N-1 assessment should be conducted for the office space above to assess flanking noise through the ventilation on the façade wall of the substation room.

## 6.1.3 PLANT NOISE IMPACT ON COMMUNAL AREAS

There are no standards or policies for the limitations of noise in a communal amenity area and therefore the common noise requirement for the communal areas in this project is adopted from the *World Health Organisation – Guidelines for Community Noise*. The noise levels from the plant shall not exceed 50 - 55 dBA in any communal areas on the development.



#### 6.1.4 PLANT NOISE WITHIN ANY AFFECTED COMMERCIAL PROPERTIES

The noise emissions from plants into the nearby commercial buildings need to be assessed according to the requirements of the acoustic environment inside the affected buildings. General noise limits inside a commercial building (general offices) is 40 dBA according to AS/NZS 2107:2000 and therefore the noise level from the plants shall not exceed 50 dBA on the façade for an operable windows and 60 dBA for fixed windows.

#### 6.1.5 CARPARK ACCESS GATES

In order to meet the requirement of noise levels no greater than 60 dBA  $L_{Amax}$  outside operable windows (as described in (Section 6.1.4), quiet operation models shall be selected with maximum noise levels produced during operation of the gate, as measured at 3 meters from the gate, not exceeding 60 dBA  $L_{Amax}$ . Gates should be fixed with vibrations mounts which are recommended by the product supplier and installed correctly. It is recommended that selected gate models be reassessed as relevant details become available at later stages of the project to ensure compliance.

#### 6.1.6 ALDI SUPERMARKET AND RETAIL STORE

Vipac recommends that the ALDI Supermarket and Retail Stores are designed and constructed using noise proofing and vibration dampening techniques to ensure that noise and vibration emitted as a result of the Store's business operations (which include extended hours unloading and store stocking) will not impact other areas of the development. Any services penetrating the ALDI Supermarket and Retail Stores tenancy building envelope must be insulated to eliminate transmission of airborne and impact generated sound from within the tenancy to other parts of the development to the relevant Australian Standards.

Mechanical services and plant noise associated with the use of the ALDI Supermarket and Retail Stores are required to comply with the *SEPP N-1* noise limits specified in Table 6-2 at the nearest affected residences. This includes noise from trucks reversing into the ALDI loading bay found on Basement Level 1. Detailed assessment of these items will be required at detailed design phase.

#### 6.2 DELIVERY TRUCKS/LOADING BAYS

In Victoria EPA Publication 1254 - *Noise control guidelines* the noise control guidelines for the deliveries to shops are provided and they are summarised below. These guidelines should be incorporated into the permit condition for delivery trucks/loading bays for this development.

Table 6-4 presents the schedule for deliveries at shops.

Table 6-4: Schedule for deliveries at shops, including truck-mounted refrigeration units		
Monday to Saturday 7 am — 10 pm		
Sundays and public holidays	9 am — 10 pm	

Note: All ancillary motors or trucks should be turned off whilst making the delivery.

For deliveries outside the hours contained in the table above the noise from deliveries should be inaudible in a habitable room of any residential properties regardless of whether any door or window giving access to the room is open. The noise mitigation shall be assessed at the detail design stage if required.



#### 6.3 GARBAGE TRUCKS

In Victoria EPA Publication 1254 - *Noise control guidelines* the noise control guidelines for the industrial waste collection are provided and they are summarised below. These guidelines should be incorporated into the permit condition for garbage trucks operating for this development.

Table 6-5 presents the schedule for garbage trucks at shops.

Table 6-5: Schedule for garbage trucks at shops
---

One collection per week			
Monday to Saturday	6:30 am — 8 pm		
Sundays and public holidays	9 am — 8 pm		
Two or more collections per week			
Monday to Saturday	7 am — 8 pm		
Sundays and public holidays	9 am — 8 pm		

In addition, the following attention should be paid.

- Refuse bins should be located at sites that provide minimal annoyance to residential premises.
- Compaction should be carried out while the vehicle is moving.
- Bottles should not be broken up at collection site.
- Noisy verbal communication between operators should be avoided where possible.



#### 6.4 NCC REQUIREMENTS FOR INTERNAL PARTITIONS

The *National Construction Code* (or *NCC*, previously known as *Building Code of Australia*) gives the requirements for sound insulation between dwellings in multi-residential buildings (Class 2).

#### 6.4.1 NCC REQUIREMENTS FOR INTER-TENANCY WALLS

The *NCC* performance requirements and deemed-to-satisfy provisions for walls are summarised in Table 6-6. This table also recalls the *NCC* requirements for doors from units to common areas (e.g. apartment entry doors).

Required airborne sound insulation performance is expressed in terms of the weighted standardized level difference  $[D_{nT,w}]$  and the weighted standardized level difference with spectrum adaptation term  $[D_{nT,w} + C_{tr}]$ . These rating indices are determined in accordance with *AS/NZS 1276.1* or *ISO 717.1* using results from in-situ measurements.

Deemed-to-satisfy provisions are expressed in terms of the weighted sound reduction index  $R_w$  and the weighted sound reduction index with spectrum adaptation term  $[R_w+C_t]$ . These rating indices are determined in accordance with *AS/NZS 1276.1* or *ISO 717.1* using results from laboratory measurements.

Partition	In-situ performance requirement	Deemed to satisfy provision
Wall separating two sole occupancy units	$D_{nT,w}\text{+}C_{tr} \geq 45 \ dB$	$R_w + C_{tr} \ge 50 \text{ dB}$
Wall separating a unit from common areas or buildings of other classification	$D_{nT,w} \geq 45 \; dB$	R <sub>w</sub> ≥ 50 dB
Door assembly in wall separating a unit from a common area	$D_{nT,w} \geq 25 \; dB$	R <sub>w</sub> ≥ 30 dB

Table 6-6: NCC Requirements for Airborne Sound Insulation of Walls and Doors

Certain walls require impact sound insulation rating and these must be of a discontinuous construction. This is summarised in Table 6-7.

Table 6-7: NCC Requirements for Impact Sound Insulation of Walls

Partition	Discontinuous construction	
Wall separating a wet area <sup>1</sup> in one unit from a habitable room (other than kitchen) in an adjacent unit	<ul> <li>for masonry wall, where wall ties are required to connect leaves, wall ties are of the resilient type</li> </ul>	
Wall separating a unit from a plant room or a lift shaft	<ul> <li>for walls other than masonry, there must be no contact between the leaves except at the periphery; a 20 mm discontinuity in the construction is required</li> </ul>	

Note: Because they share the same space as living room areas, **open kitchen** areas are considered habitable rooms when they are receiving rooms and wet areas when they are source rooms.

<sup>&</sup>lt;sup>1</sup> a bathroom, a sanitary compartment, a laundry or a kitchen



#### 6.4.2 NCC REQUIREMENTS FOR FLOORS

The NCC performance requirements and deemed-to-satisfy provisions for floors are summarised in Table 6-8.

Required airborne sound insulation performance of floors and deemed to satisfy provisions are expressed in terms of  $[D_{nT,w}+C_{tr}]$  and  $[R_{w}+C_{tr}]$ , respectively.

Required impact sound insulation performance of floors is expressed in terms of the weighted standardised impact sound level [ $L_{nT,w}$ ]. This rating index is determined in accordance with *AS ISO 717.2-2004* using results from in-situ measurements.

Deemed-to satisfy provisions are expressed in terms of the weighted normalised impact sound level  $[L_{n,w}]$ . This rating index is determined in accordance with *AS ISO 717.2-2004* using results from laboratory measurements.

An acoustic underlay should be added to roof top areas directly above apartments to reduce impact noise below and achieve an  $L_{nT,w} \leq 50$  dB.

Insulation Type	In-situ performance requirement	Deemed to satisfy provision	
Airborne sound insulation of floors	$D_{nT,w} \text{+} C_{tr} \geq 45 \text{ dB}$	$R_w \ + C_{tr} \geq 50 \ dB$	
Impact sound insulation of floors	$L_{nT,w} \leq 62 \; dB$	$L_{n,w} \leq 62 \ dB$	

Table 6-8: NCC Requirements for Airborne and Impact Sound Insulation by Floors

#### 6.4.3 NCC REQUIREMENTS FOR SERVICES DUCTS AND PIPES

Ducts and pipes for storm water, soil waste or water supply that serve or pass through more than one unit must be contained by a construction providing sound insulation. The NCC criterion for airborne sound insulation performance of this partition is recalled in Table 6-9.

Table 6-9: NCC Requirements for Sound Insulation of Ducts	and Pipes
---	-----------

Room	Required Airborne Sound Insulation Rating
Habitable room (other than kitchen)	$[R_w + C_{tr}] \geq 40 \ dB$
Kitchen or non-habitable room	$[R_w+C_{tr}] \ge 25 \text{ dB}$

Note: Because they share the same space as living room areas, **open kitchen** areas are considered habitable rooms when they are receiving rooms and wet areas when they are source rooms.



## 7 BUILDING FAÇADE GLAZING RECOMMENDATIONS

The façade glazing for habitable rooms, retail stores, office space and the ALDI Supermarket will be designed based on measured traffic noise and a truck reversing noise spectrum. For habitable rooms the limits will be  $L_{Aeq,8hr} = 35 \ dBA$  for bedrooms and  $L_{Aeq,16hr} = 40 \ dBA$  living areas. For Office Space, the AS/NZS 2107 Standards recommends  $L_{Aeq} = 40 \ to \ 45 \ dB(A)$ ,  $L_{Aeq} = 50 \ dBA$  for Small Retail Stores and  $L_{Aeq} = 55 \ dBA$  for Supermarkets. The spectrum measured during peak traffic flow conditions will be used to achieve noise limits listed in Table 6-1.

The following room finishes are assumed for glazing designs.

- Walls and ceiling: plasterboard
- Floor: carpet for bedrooms, office space and potential sub tenancy, timber floor for living areas and concrete for supermarket and shops

Glazing							Rw		
No.	No.		125	250	500	1000	2000	4000	
Aldi Supermarket Basement 1									
1	Aldi	21	24	26	31	34	29	33	31
Office, Sub Tenancy and Retail Stores Ground Floor									
1	Office	21	24	26	31	34	29	33	31
5	Potential Sub Tenancy	25	28	30	36	41	41	46	39
1	Retail G12,G14,G15,G16,G17	21	24	26	31	34	29	33	31
2	Retail G13	22	25	29	34	34	33	40	33
	Apartment	s facin	g White	horse l	Road (F	loors 1	to 4)		
8	Bed Room	27	30	30	39	44	45	55	42
5	Living Room	25	28	30	36	41	41	46	39
	Apartme	nts fac	ing Rai	lway Ro	oad (Flo	ors 1 to	4)		
7	Bed Room	26	27	26	37	44	46	50	41
5	Living Room	25	28	30	36	41	41	46	39
Apartments facing inside (Floors 1 to 4)									
6	Bed Room	25	26	26	35	43	44	48	39
4	Living Room	25	28	27	34	41	39	47	38
Office Space (Floors 1 to 4)									
3	Office side facing Whitehorse Road	23	26	23	32	40	38	45	35
1	Office side facing	21	24	26	31	34	29	33	31

#### Table 7-1: Minimum transmission loss for glazing

Pace Development Group Pty Ltd



160 Whitehorse Road Stage 2 - Acoustics Town Planning

Acoustic Town Planning Report

	Railway Road								
	Office Space (5 <sup>th</sup> Floor)								
1	Office	21	24	26	31	34	29	33	31
	Apartments facing Whitehorse Road (Floors 5 to 6)								
5	Bed Room	25	28	30	36	41	41	46	39
4	Living Room	25	28	27	34	41	39	47	38
	Apartments facing Railway Road and Inside (Floors 5 to 6)								
4	Bed Room	25	28	27	34	41	39	47	38
1	Living Room	21	24	26	31	34	29	33	31

Operable windows must be fitted with acoustic seals to ensure the acoustic performance of the glazing is not compromised. In addition to the provision of suitable glazing requirements, minimum R<sub>w</sub> ratings for window systems are provided to ensure the performance of the glazing will not be compromised by frames and seals.

Ventilation ducts on facade need to be assessed during the design and development stage to ensure internal requirements are achieved.

For living room areas where operable windows are desired, awning type windows are preferred in terms of achieving an effective acoustic seal. However, sliding windows are acceptable provided they include tight fitting seals. Care should be taken to ensure that all external sliding glass doors are proprietary acoustic door sets with integral frame and seals.

It should be noted that the minimum glazing requirements specified in this report are based on assumed glazing and room dimensions. If the ratio glazing area to room area differs significantly from the assumed values in Table 7-1, further assessment of glazing will be required.

Glazing reference No.	Octave band central frequency (Hz)					Rw		
	63	125	250	500	1000	2000	4000	
1	21	24	26	31	34	29	33	31
2	22	25	29	34	34	33	40	33
3	23	26	23	32	40	38	45	35
4	25	28	27	34	41	39	47	38
5	25	28	30	36	41	41	46	39
6	25	26	26	35	43	44	48	39
7	26	27	26	37	44	46	50	41
8	27	30	30	39	44	45	55	42


Table 7-2 - Glazing Numbers Spectrum

Pace Development Group Pty Ltd

160 Whitehorse Road Stage 2 - Acoustics Town Planning

Acoustic Town Planning Report






30U-18-0958-TRP-6757059-2

Commercial-In-Confidence

Pace Development Group Pty Ltd 160 Whitehorse Road Stage 2 - Acoustics Town Planning

Acoustic Town Planning Report





30U-18-0958-TRP-6757059-2


Commercial-In-Confidence

ViPAC

Pace Development Group Pty Ltd

160 Whitehorse Road Stage 2 - Acoustics Town Planning

Acoustic Town Planning Report





## 8 CONCLUSION

With the recommended noise attenuation measures, the internal spaces within the development should meet the recommended noise criteria. With appropriate noise attenuation, the development should not produce noise that exceeds the recommended criteria at surrounding properties.

Vipac Engineers and Scientists Ltd (Vipac) have been engaged by *Pace Development Group* to provide acoustic consulting services for the development at 160 Whitehorse Road, Blackburn Stage 2. The assessments contained within this document follow the methodology and criteria specified in relevant Australian standards and guidelines. If the recommendations in this report are followed the development is predicted to comply with the provided assessment criteria.



## Appendix A GLOSSARY

Term	Definition
dB	Decibel Magnitude of the sound pressure level.
dBA	A-weighted Decibels. The 'A'-weighting adjusts the measured levels to better reflect the sensitivity of the human ear to different frequencies.
L <sub>Aeq,T</sub>	The A-weighted continuous equivalent sound pressure level. It is defined as the steady sound level that contains the same amount of acoustical energy as the corresponding time-varying sound.
L <sub>A90,T</sub>	The A-weighted sound pressure level exceeded for 90% of the measurement period. LA90 is used in Victoria as the descriptor for background noise level.
Sound pressure level	The ratio in decibels (dB) of the sound pressure at a given receiver position to a reference pressure of 2.10 <sup>5</sup> Pa. The sound pressure level depends, amongst other parameters, on the sound power level of the source and the distance separating the source and the receiver.



## **Appendix B INSTRUMENTATION**

Instrument	Model/Type	Serial No.	Next Calibration
Bruel & Kjaer sound level meter (type 1)	2250	2690200	16/01/2020
Bruel & Kjaer calibrator	4231	1139057	25/07/2019
01dB Metravib Logger	DUO	10272	24/08/2019
01dB Metravib Logger	DUO	10292	24/08/2019

**End of Report**